BRANSON PRINTWORKS

Panel & installation guide

INSTALLATION GUIDE

Total: $0.00

Review the selected material manufacturer installation instructions. Confirm the existing wall or floor, its texture and finish, and the exact material approved for that surface. Preparation differs for smooth drywall, textured walls, masonry and floors. Follow the product-specific requirements for cleaning, repairs, moisture, paint curing, primers, adhesives, laminates and any test application. Do not start until the preparation plan is confirmed. Check panel numbering and the supplied schematic before hanging. Dry fit and verify the artwork orientation. Align printed registration and matched seams using the manufacturer specified method. Do not assume all materials support the same overlap or butt joint. Allow for trim. Protect finished panels and follow material-specific cleaning guidance. Contact the studio before proceeding if surfaces, color, measurements, or panels differ from the approved proof.
Branson, Missouri | support@bransonprintworks.com